

No: DSIIDC/EE(ED-III)/Corrigendum/2023-24/57

Dated: 16.11.2023

CORRIGENDUM-II

Name of work: - Servicing and repairing of Air-Cooled HVAC Plant having capacity of 2X150TR (in all respect) installed at PSK, Laxmi Nagar, Delhi.
Tender ID: 2023_DSIDC_249588_1
Tender Ref. No.: 01/23-24

In continuation to earlier corrigendum No. DSIIDC/EE(ED-III)/corrigendum/2023-24/56, Dated: 07.11.2023 and with reference to different enquiries from various agencies, the further necessary amendments have been considered as follows:


1. Point at Sr. No. 1 of above-mentioned Corrigendum, will be read as "Cooling Coil section with aluminium finned copper tubes (tubes thickness not less than 0.5mm) of 6 row deep is required".
2. Size of Cooling Coils for different capacity of AHUs are as required, as below:

Air Flow (CFM)	4,000 CFM	7,500 CFM	10,000 CFM	12,000 CFM	16,000 CFM	30,000 CFM	Remarks
Fin Height (mm) (Approx.)	635	952.5	1206.5	1206.5	1524	1016	The final size of the Coils may be worked out as per physically verification.
Fin Length (MM) (Approx.)	1171	1464	1540	1850	1950	2744	

3. Make for AHUs and cooling coils are revised as Zeco/Voltas/Suvidha/LG/Edgetech/ Ravi Aircon/ Universal/ or equivalent.
4. IE-2 / IE-3 type of Motors are required.

The Last dates for downloading of Tender, Bid Submission & opening of Technical Bid are further revised as under:

Last date & time for download of tender document & bid submission.	23/11/2023, 3:00PM
Date & Time of opening of technical bid.	23/11/2023, 3:30 PM
Date & Time of opening of financial bid.	To be informed later on



(Sunil Kumar)
Executive Engineer (ED-III)

Divisional Manager (IT)